

## Bill of Quantity (BoQ)

Interior Fit-out Works of Proposed Country Office of HBL Bangladesh  
Address: Autograph (Level 04), 67 & 68 Kemal Ataturk Avenue, Banani, Dhaka 1213

<b>SUMMARY OF SCHEDULE OF ITEMS</b>	<b>AMOUNT</b>
A. Civil Works	BDT
B. Paint Works	BDT
C. Feature Panel Work	BDT
D. Partition Work	BDT
E. Floor Finishing Work	BDT
F. Ceiling Work	BDT
G. Door Work	BDT
H. Plumbing & Sanitary Work	BDT
I. Electrical Works	BDT
J. Miscellaneous Work	BDT
K .Furniture Work	BDT
<b>TOTAL AMOUNT BDT</b>	

**In Word (Taka) :**

**DATE** : \_\_\_\_\_

**NAME OF THE COMPANY** : \_\_\_\_\_

**NAME OF THE OWNER** : \_\_\_\_\_

**COMPANY SEAL** :

**AUTHORIZED PERSON** : \_\_\_\_\_ **SIGNATURE** \_\_\_\_\_

**ATTESTED BY THE OWNER** : \_\_\_\_\_ **SIGNATURE** \_\_\_\_\_

**Schedule of Items**  
**Interior Fit-out Work of Proposed Country Office of HBL Bangladesh**

SL	Description	QTY	Unit	Unit Rate	Amount (BDT)
<b>A. Civil Works</b>					
1	<b>250mm BRICK WORK :</b> Supply, fitting & fixing of Brick work with First Class Brick (Size: 237mm X 125mmX 68mm) in cement sand (F.M. 1.2) mortar (1:6) in any structure in/c racking out joints, cleaning and soaking the brick at least for 24 hrs before use, filling the interstices with mortar, water, electricity, curing at least for 07 (Seven) days with scaffolding etc. all complete as per Bank standard and full satisfaction of the Bank authority.	880	Sq. ft		
2	<b>125mm BRICK WORK:</b> Supply, fitting & fixing Brick work with First Class Brick (Size: 237mm X125mm X68mm) in cement sand (F.M. 1.2) mortar (1:6) in any structure in/c racking out joints, cleaning and soaking the brick at least for 24 hrs before use, filling the interstices with mortar, water, electricity, curing at least for 07 (Seven) days with scaffolding etc. all complete as per Bank standard and full satisfaction of the Bank authority.	920	Sq. ft		
3	<b>PLASTER WORK:</b> Supply, fitting & fixing Minimum 12mm @ wall, 6mm @ roof thick plaster with cement sand plastering (F.M. 1.2) plaster (1:4) best quality cement to walls both inner & outer surfaces. R.C.C. surfaces finishing corners and edges including washing of sand cleaning the surface, scaffolding, water, electricity and curing at least for 07 (Seven) days etc. all complete as per Bank standard and full satisfaction of the Bank authority.	1995	Sq. ft		
4	<b>CC CASTING:</b> Supply, fitting & fixing 50mmX50mm cement concrete works using wooden shutter with minimum cement content relates to mix ratio 1:1.5:3 having best quality coarse sand and 12mm down well grade brick chips including standard mixer machine washing of sand cleaning the surface, scaffolding, water, electricity and curing at least for 07 (Seven) days etc. all complete as per Bank standard and full satisfaction of the Bank authority.	150	Cft		

SL	Description	QTY	Unit	Unit Rate	Amount (BDT)
5	<p><b>RCC WORKS FOR LINTEL:</b> Supply, fitting &amp; fixing 150mmX150mm Lintel Double Layer Reinforcement cement concrete works using wooden shutter with minimum cement content relates to mix ratio 1:1.5:3 having best quality coarse sand and 12mm down well grade brick chips including standard mixer machine washing of sand cleaning the surface, scaffolding, water, electricity and curing at least for 07 (Seven) days etc. all complete as per Bank standard and full satisfaction of the Bank authority.</p>	70	Rft		
<b>Sub-total of Civil Works (BDT)</b>					
<b>B. Paint Works</b>					
6	<p><b>PLASTIC PAINT (Berger) :</b> Supply, Fitting &amp; Fixing Plastic emulsion paint of approved best quality and color delivered from authorized local agent of the manufacturer in a sealed container, applying to wall and ceiling in three coats over a lime putty of branch specified brand applied on primer or sealer elapsing specified time for drying/recoating including cleaning drying, making free from dirt, grease, wax, removing all chalked and scaled materials, fungus, mending good the surface defects, sand preparing the surface and necessary scaffolding, spreading by brush/roller/spray etc. All complete as per bank standard and full satisfaction of the bank authority.</p>	21010	Sq. ft		
<b>Sub-total of Paint works (BDT)</b>					
<b>C. Feature Panel Work</b>					
7	<p><b>CONCRETE TILES FEATURE WALL :</b> Supply, fitting and fixing of Concrete Tiles on Wall 100mm x 600mm with thickness between 18mm to 25mm, made with a combination of local, sylhet sand, white cement, 18mm stone chips, wire mesh, ad-mix chemical etc. including including metal ms clamps for suport, cutting, laying and hire charge of machine and finishing with care, 07 days curing etc. including water, electricity and other charges all complete as per Bank standard and full satisfaction of the Bank authority.</p>	1800	Sq. ft		
8	<p><b>WORLD MAP FEATURE WALL :</b> Supply, fabrication &amp; installation of World Map made of 18 mm approved color panel on both sides on 10mm tempered glass including supply of necessary hardware, lighting, consumables, scaffolding etc. fitted with necessary accessories like rivet, screw, rowel bolt, black rubber in groves, welded framing etc. all complete as per design, direction and full satisfaction of the Bank authority. Apx. 77 sft.</p>	1	Nos		
<b>Sub-total of Feature Panel Work (BDT)</b>					

SL	Description	QTY	Unit	Unit Rate	Amount (BDT)
<b>D. Partition Work</b>					
9	<b>FROSTED PAPER :</b> Supply, fitting & fixing of Printed Frosted Paper As Per Design, Height 1200 mm all complete as per design, direction and full satisfaction of the Bank authority.	1100	Sq. ft		
10	<b>10 MM GLASS PARTITION WITH U Channel:</b> Supply, fitting & fixing glass partition made of 10 mm Tempered Clear Glass (China/Nasir or equivalent) with 25mmX25mm aluminum U channel in all sides of approved brand (KAI/FUWANG) and color with edge polish in vertical portion of glass, water color silicon gum by using masking tape including all other accessories and hardware etc. all complete as per Bank standard and full satisfaction of the Bank authority.	1980	Sq. ft		
11	<b>FULL HEIGHT PARTITION :</b>				
	<b>a) OAK Board Dry Partition:</b> Supply, fitting & fixing of 75mm Dry Partition with 18mm thick OAK Veneer board (Premium Quality) with best quality framing for adequate strength, including all other accessories and hardware, rowel plug & 75mm screw, nail etc with top quality <b>Natural Polish</b> all complete as per Bank standard and full satisfaction of the Bank authority.	395	Sq. ft		
	<b>b) Glass Wool Partition:</b> Supply, fitting & fixing of 12mm thick both side gypsum board (Elephant Brand) with best quality 40mm Glass Wool, 1.5mm X 50mm C Channel frame, at 600X600mm in grid suspended from ceiling, roof, floor, RCC and wall or beam by rowel plug & 75mm screw, nail etc with <b>03 coat of paint</b> , all complete as per Bank standard and full satisfaction of the Bank authority.	100	Sq. ft		
	<b>c) Dry Partition:</b> Supply, fitting & fixing of 12mm thick both side gypsum board (Elephant Brand) with best quality 1.5mm X 50mm C channel frame, at 600X600mm in grid suspended from ceiling, roof, floor, RCC and wall or beam by rowel plug & 75mm screw, nail etc with <b>03 coat of paint</b> All complete as per Bank standard and full satisfaction of the Bank authority.	4340	Sq. ft		
		<b>Sub-total of Partition Work (BDT)</b>			
<b>E. Floor Finishing Work</b>					

SL	Description	QTY	Unit	Unit Rate	Amount (BDT)
12	<p><b>MARBLE (LIGHT) :</b> Supply, fitting &amp; fixing of 1200mmX600mm Marble Slab with fully polished finish of approved sample similar to existing Marble Slab floor in Lobby Area with 40 mm thick cement sand (F.M. 1:2) mortar(1:3) and raking out the joints with respective jointer filter and binder including cutting, laying and hire charge of machine and finishing with care etc including water electricity and other charges all complete with care and finish the pointing work including 100mm height skirting etc. with 07 days curing etc. all complete as per Bank standard and full satisfaction of the Bank authority.</p>				
	a) Marble Floor for Reception Area - 600mm x 600mm	400	Sq. ft		
	b) Marble Border for Corridor Area - 1200mm x 150mm	350	Sq. ft		
	<b>Tiles :</b>				
13	<p><b>MARBLE TEXTURE TILES FOR CORRIDOR AREA - 1200mm x 600mm</b> Supply, fitting &amp; fixing of imported homogenous tiles (Venuss/Sheltech equivalent) of approved color on floor with 40mm thick cement (F.M. 1:2) mortar (1:3) base and raking out the joints with respective joint filter and binder including cutting, laying and hire charge of machine and finishing with care, 07 days curing etc. including water, electricity and other charges All complete as per Bank standard and full satisfaction of the Bank authority.</p>	1250	Sq. ft		
14	<p><b>MATT TILES FOR GENERAL WORK AREA : 600mm x 600mm</b> Supply, fitting &amp; fixing of best quality (Grade-A) homogenous tiles (Venuss/ Sheltech/ DBL/ Charu equivalent) of approved color on floor with minimum 40mm thick cement (F.M. 1:2) mortar (1:3) base and raking out the joints with respective joint filter and binder including cutting, laying and hire charge of machine and finishing with care, 07 days curing etc. including water, electricity and other charges All complete as per Bank standard and full satisfaction of the Bank authority.</p>	4500	Sq. ft		
15	<p><b>WOODEN TEXTURE TILES : Imported (Spain) - 200mm x 1200mm</b> - Supply, fitting &amp; fixing of best quality imported Spanish homogenous tiles of approved color on floor with minimum 40mm thick cement (F.M. 1:2) mortar (1:3) base and raking out the joints with respective joint filter and binder including cutting, laying and hire charge of machine and finishing with care, 07 days curing etc. including water, electricity and other charges All complete as per Bank standard and full satisfaction of the Bank authority.</p>	1390	Sq. ft		

SL	Description	QTY	Unit	Unit Rate	Amount (BDT)
16	<b>TILES FOR SERVICE AREA - 600mm x 600mm</b> Supply, fitting & fixing of best quality (Grade-A) homogenous tiles (Venuss/ Sheltech/ DBL/ Charu equivalent) of approved color on floor with minimum 40mm thick cement (F.M. 1:2) mortar (1:3) base and raking out the joints with respective joint filter and binder including cutting, laying and hire charge of machine and finishing with care, 07 days curing etc. including water, electricity and other charges All complete as per Bank standard and full satisfaction of the Bank authority.	650	Sq. ft		
17	<b>COUNTRY MANAGER TOILET TILES FOR FLOOR AND WALL - 300mm x 600mm</b> - Supply, fitting & fixing of best quality (Grade-A) homogenous tiles (Venuss/ Sheltech/ DBL/ Charu or equivalent) of approved color on floor with minimum 40mm thick cement (F.M. 1:2) mortar (1:3) base and raking out the joints with respective joint filter and binder including cutting, laying and hire charge of machine and finishing with care, 07 days curing etc. including water, electricity and other charges All complete as per Bank standard and full satisfaction of the Bank authority.	200	Sq. ft		
18	<b>TILES FOR COMMON AREA : Local DBL/CHARU/RAK - 600mm x 300mm</b> Supply, fitting & fixing of best quality (Grade-A) homogenous tiles (Venuss/ Sheltech/ DBL/ Charu equivalent) of approved color on floor with minimum 40mm thick cement (F.M. 1:2) mortar (1:3) base and raking out the joints with respective joint filter and binder including cutting, laying and hire charge of machine and finishing with care, 07 days curing etc. including water, electricity and other charges All complete as per Bank standard and full satisfaction of the Bank authority.	640	Sq. ft		
19	<b>TILES FOR FEATURE WALL FOR RECEPTION AREA - 1200mm x 600mm</b> Supply, fitting & fixing of best quality (Grade-A) homogenous tiles (Venuss/ Sheltech/ DBL/ Charu equivalent) of approved color on floor with minimum 40mm thick cement (F.M. 1:2) mortar (1:3) base and raking out the joints with respective joint filter and binder including cutting, laying and hire charge of machine and finishing with care, 07 days curing etc. including water, electricity and other charges All complete as per Bank standard and full satisfaction of the Bank authority.	250	Sq. ft		
20	<b>RAISED SERVER FLOOR</b> Supply, fitting and fixing of Anti-Static Flooring 600mm x600mm with adjustable pedestal galvanised steel support with a minimum height of 300m - 450mm, min 25% perforated floor for cable ventilation, strong load bearing capacity, shockproof including all accessories, materials, labour costs and charges all complete as per Bank Standard and full satisfaction of the Banking Authority.	405	Sq. ft		
<b>Sub-total of Floor Finishing Works (BDT)</b>					

SL	Description	QTY	Unit	Unit Rate	Amount (BDT)
<b>F. Ceiling Work</b>					
21	<p><b>LOUVRE DESIGN BOARD CEILING:</b> Supply, fitting &amp; fixing of Designed Louvre Ceiling made with 18mm Commercial Board (Partex or equivalent) premium quality false ceiling and 03 (Three) coats of plastic paint over primer coat, putty, racking out joints etc. Also including powder coated T-bar of section 25mmx38mm and L-angle of section 25mmx25mm at edges, at 600mmx600mm grid suspended ceiling by rowel plug iron angles 12 SWG G.I. wire, screws, hooks, nails etc. maintaining straight lines and desired finished level at bottom face with vertical or beams by electric drill machine damage if any during the materials, accessories, scaffolding, labor for Installation etc. all complete as per Bank standard and full satisfaction of the Bank authority.</p>	1350	Sq. ft		
22	<p><b>GRID CEILING:</b> Supply, fitting &amp; fixing of Grid Ceiling (Color: Grey) made of PVC composite with 600mm x 600mm panel size, grid gap 100mm x 100mm, Heat Insulation, Moisture-Proof, Mould-Proof, Smoke-Proof also ceiling over powder coated T-bar of section 25mmx38mm and L-angle of section 25mmx25mm at edges, at 600mmx600mm grid suspended ceiling by rowel plug iron angles 12 SWG G.I. wire, screws, hooks, nails etc. maintaining straight lines and desired finished level at bottom face with vertical or beams by electric drill machine damage if any during the materials, accessories, scaffolding, labor for Installation etc. all complete as per Bank standard and full satisfaction of the Bank authority.</p>	1320	Sq. ft		
23	<p><b>OAK WOOD CEILING:</b> Supply, fitting &amp; fixing of OAK Veneer Board Ceiling (Color: Natural Polish) made of 18mm Oak Veneer Board ceiling over powder coated T-bar of section 25mmx38mm and L-angle of section 25mmx25mm at edges, at 600mmx600mm grid suspended ceiling by rowel plug iron angles 12 SWG G.I. wire, screws, hooks, nails etc. maintaining straight lines and desired finished level at bottom face with vertical or beams by electric drill machine damage if any during the materials, accessories, scaffolding, labor for Installation etc. all complete as per Bank standard and full satisfaction of the Bank authority.</p>	420	Sq. ft		
24	<p><b>SOLID &amp; PERFORATED BOTTOM PERFORATED CABLE TRAY:</b> Supply, Fitting &amp; Fixing Length:Max 6000mm, Steel thickness:0.8-3mm perforated cable tray perforated cable tray, Side Rail Height:50-200mm,Width:Max 1000mm etc All complete as per Bank standard and full satisfaction of the Bank authority.</p>	600	Rft		

SL	Description	QTY	Unit	Unit Rate	Amount (BDT)
25	<b>KEROSHIN WOODEN LIGHTING TRAY</b> :Supply, Fitting & Fixing of 25mm thick Keroshin wood lighting tray, with 6mm SS chain etc with top quality <b>Natural Polish</b> all complete as per Bank standard and full satisfaction of the Bank Authority.	750	Rft		
26	<b>WOODEN DROP for GLASS AND DRY PARTITION</b> : Supply, fitting & fixing of plain wooden drop over the glass and dry partition suspended from existing R.C.C. slab of the building at the level of 2400mm (or as per direction) from floor level made of 12mm thick white partex over frame of section 75mm X 38mm at 600mm X 600mm in grid suspended from ceiling or roof with 50mm x 25mm best quality seasoned Garjon wood section, 75mm screw, nails, rowel plug, fevicol aica and <b>03(Three) coats of plastic paint over primer coat</b> , putty, racking out joints etc. all complete as per Bank standard and full satisfaction of the Bank Authority.	520	Rft		
<b>Sub-total of Ceiling Works (BDT)</b>					
<b>G. Door Work</b>					
27	<b>TEMPERED DOOR (900mmx2400mm):</b> Supply, fitting & fixing of imported 10 mm glass door shutter (V.V.P) with door closer at lower side, 1200mm round wooden handle, lower side lock, hinge, 02 nos stopper (China-Half round SS, rubber coating) & other accessories etc. all complete as per Bank standard and full satisfaction of the authority.	25	Nos		
28	<b>SLIDING TEMPERED DOOR (1500mmx2400mm):</b> Supply, fitting & fixing of imported 10 mm Temperd glass door with EDF Aluminium Frame, Middle side lock, hinge, 02 nos stopper (China-Half round SS, rubber coating) & other accessories etc. all complete as per Bank standard and full satisfaction of the authority.	280	Sq. ft		
29	<b>EMERGENCY FIRE EXIT DOOR :</b> Supply, fitting & fixing UL Approved, Fire Rating: 120 Minutes, Size: L-1100 x H-2400 mm, Door Model: Multiline Industries Ltd, Door Core: Rock wool with density 100 kg/m3, Door Sheet Thickness: 1.6mm, Door Thickness: 50mm all complete as per Bank standard and full satisfaction of the authority.	4	Nos		
30	<b>FLUSH DOOR SHUTTER WITH FRAME :</b> Supply, fitting & fixing of 38mm thick and having density 400kg/cum solid particle board single leaf flush door (Brand: Partex or equivalent) of best quality teak veneered partex door, frame by best quality seasoned Gorjon wood 62mmx125mm section with the supply of best quality all hardware, 100mm metal hinges, clamps, sitkani, coal tarring of frame including, 02 nos stopper (China-Half round SS, rubber coating), 150mm long tower bolt (Imported), with <b>Polish finish of approved color</b> , all complete as per direction and full satisfaction of the Bank Authority.	6	Nos		



SL	Description	QTY	Unit	Unit Rate	Amount (BDT)
31	<b>DOOR CLOSER:</b> Supply, fitting & fixing of Imported door closer (China) of approved quality (New star) in position including all required accessories ensuring minimum injury to door shutter and frame etc. all complete as per Bank standard and full satisfaction of the Bank authority.	6	Nos		
<b>Sub-total of Door Work (BDT)</b>					
<b>H. Plumbing &amp; Sanitary Work</b>					
32	<b>COUNTER/ PADEL STAND BASIN :</b> Supply, fitting & fixing of basin (RAK –Karla & Mira) of approved color/ Ivory color with other fittings etc. all complete as per full satisfaction of the Bank authority.	1	Nos		
33	<b>MIRROR with Frame/SS Knob:</b> Supply, fitting & fixing 6mm thick mirror (900mm X 750mm) with Aluminium Section Frame (Grey) of best quality with necessary hardware etc. all complete as per full satisfaction of the Bank authority.	1	Nos		
34	<b>STEEL SINK (Round):</b> Supply, fitting fixing of single bowl stainless steel sink (size: 450mm dia) with heavy type ( Singapore/Malaysia) CI steel brackets 40mm dia CP chain plug, 40mm dia CP waste, 40mm dia PVC waste pie with brass coupling (750mm length) including making hole in wall and floor and mending good the damages, finishing with cement mortar all complete as per full satisfaction of the Bank authority.	2	Nos		
35	<b>SANITARY FITTINGS:</b> Supply, fitting & fixing of toilet fittings of approved quality with necessary hardware etc. all complete as per full satisfaction of the Bank authority. (Nazma)				
	a) Tri Star Left Hand Sink Cock (Nazma)	1	Nos		
	b) Six Corn Angle Stop Cock (Nazma)	1	Nos		
	c) Single Liver Wash Basin Mixer (Nazma)	1	Nos		
	d) Germany Style Bottle Tarff (Nazma)	1	Nos		
	e) Tri Star Twin One Bib Cock(Nazma)	1	Nos		
	f) Square SS Floor Grating Net (Wesda)	1	Nos		

SL	Description	QTY	Unit	Unit Rate	Amount (BDT)
	<p><b>g) SANITARY PIPING WORKS:</b></p> <p>i. Supply, fitting and fixing of 25mm/18mm G.I./Upvc pipe with all general fitting such as bend, elbow, socket, reducing socket, Tee, unions, jam-nuts, gate valve for each toilet and kitchen including cutting trenches where necessary and fitting the same with earth duly rammed and fixing in walls with holder, bats and making hole in floor, walls and consequent mending good the damages etc all complete from building main line to the desired areas of usage.</p> <p>ii. Supply fitting and laying up to depth of invert 100mm inside dia best quality UPVC C grade pressure soil pipe having specific gravity 1.3-1.45 and other physical, chemical, thermal, fire resistivity properties etc as per BSTI approved manufacturer standards or ASTM, BS/ISO/IS standards fitted &amp; fixed in position with sockets, bends, door tee, elbow, Tee with all accessories such as solvent cement, round grating/domed roof grating etc <u>from the available line to wash rooms to the disposal line</u> all complete as per Bank standard and full satisfaction of the Bank authority.</p>	1	As Required		
<b>Sub-total of Plumbing &amp; Sanitary Work (BDT)</b>					
<b>I. Electrical Work</b>					
36	PVC Conduit (Pipe Fitting for <b>AC water line</b> , Electric, CCTV, Time Attendance, HT cable & Generator cable):				
	Supply, fitting & fixing of water grade PVC rigid/flexible conduit (Aziz Pipes or equivalent) of following sizes through brick wall, RCC slab, false ceiling etc including groove cutting, network pipe, necessary binding wire & fixing circular boxes, junction boxes, sockets, fish wire, all are accessories and including mending good all damages etc. all complete as per direction and full satisfaction of the Bank authority.				
	a) 18mm dia PVC Conduit PVC Conduit	4500	Rft		
	b) 25mm dia PVC Conduit	9500	Rft		
	c) 25mm dia Flexible PVC Conduit	1000	Rft		
	c) 18mm dia Flexible PVC Conduit	2500	Rft		
	c) 9mm dia Flexible PVC Conduit	1000	Rft		
37	<b>Cable (B.R.B or Equivalent)</b>				
	Supply, fitting & fixing of PVC insulated or PVC sheathed cable (Color-Red, yellow, black) through PVC conduit in concealed, Underground, surface including all necessary fitting, fixing PVC type, fish wire, soldering, connection etc. all complete as per direction and full satisfaction of the Bank authority.				
	a) 1X50 rm (19-w) NYY Cable	250	Rft		

SL	Description	QTY	Unit	Unit Rate	Amount (BDT)
	b) 1X35 rm (7-w) NYY Cable	200	Rft		
	c) 1X16.0 rm NYY (7-w) Cable	1900	Rft		
	d) 1X6.0 rm BYA (7-w) Cable	950	Rft		
	e) 1X4 rm BYA (7-w) Cable	15000	Rft		
	f) 1X2.5 rm BYA (7-w) Cable	14000	Rft		
	f) 1X1.5 rm BYA (7-w) Cable	19500	Rft		
	g) 02 pair telephone cable	11500	Rft		
	g) RG-6 Cable (for TV)	656	Rft		
<b>38</b>	<b>Earthing Wire (B.R.B or equivalent):</b>				
	Supply, fitting & fixing ECC(Earth Continuity conductor) copper wire for earthing connection (Color-Green) through PVC conduit in concealed, Underground, surface including all necessary fitting , fixing PVC type, fish wire, soldering, connection etc. all complete as per direction and full satisfaction of the Bank authority.				
	a) 1X25 rm (19-w)BYA CableECC Wire(Green)	60	Rft		
	b) 1X16 rm (7-w)BYA Cable Wire(Green)	600	Rft		
	c) 1X4 rm (7-w)BYA Cable Wire(Green)	7500	Rft		
	d) 1X2.5 rm (7-w)BYA Cable Wire(Green).	7000	Nos		
<b>39</b>	<b>Switch/Junction Box fitting:</b>				
	Supply, fitting & fixing of different size of concealed boards/boxes (Brand– best quality local) in position including ebonite cover etc. In position with fixing of necessary, washers etc. all complete as per drawing, direction and full satisfaction of the Bank authority.				
	a) Steel/MK Plastic box(1-Gang)	100	Nos		
	a) Steel/MK Plastic box(2-Gang)	100	Nos		
	a) Steel/MK Plastic box(3-Gang)	300	Nos		
<b>40</b>	Fixing of SDB, BD and EDB boxes <b>with indicator &amp; selection switch:</b>				

SL	Description	QTY	Unit	Unit Rate	Amount (BDT)
	a) Providing & fixing 400/440V, 50 Hz grade following sub-distribution board made of 18-SWG MS sheet complete hinged type door, built-in type locking arrangement, one no. 100Amps/160amps capacity bus-bar with required no. of holes thereon on insulators at both ends, copper blocks for neutral and earth terminal, SPMCBs manufactured and tested in accordance with relevant IEC/VDE/NEMA/BS/JIS standard having minimum breaking capacity 25-KA with terminal over current and instantaneous electromagnetic short ckt. Release, necessary arrangement for fixing MCBs in/c stove enamel/grey hammer painting of board etc.				
	i. MDB Box	1	Nos		
	ii. 160amps TP MCCB ( Main Breaker)	1	Nos		
	iii. 100amps TP MCCB ( Main Breaker)	2	Nos		
	iv. 40/60amps TP MCCB	6	Nos		
	v. 30amps TP MCB	6	Nos		
	vi. 20amps SP MCB	60	Nos		
	vii. 16amps SP MCB	80	Nos		
	viii. 10amps SP MCB	50	Nos		
	ix) DP USP,BD Light & Power,DB Server	5	Nos		
41	<b>M.K /Legrand Switch:</b>				
	Supply, fitting & fixing of 250 volts 5/6amps(minimum) concealed type MK (Singapore) switch on steel/PVC/ junction MK board including necessary connection and fixing screws, PVC tape etc. all complete as per drawing, direction and full satisfaction of the Bank authority.				
	a) 2-gang switch	20	Nos		
	b) 3-gang switch	40	Nos		
	c) 4-gang switch	50	Nos		
	d) DP Switch [20AMP] for signboard	20	Nos		
42	<b>Legrand/M.K (Singapore) outlet and power socket:</b>				

SL	Description	QTY	Unit	Unit Rate	Amount (BDT)
	<b>Legrand/M.K (Singapore) outlet and power socket:</b> Supply, fitting & fixing concealed type Legrand/MK (Singapore) socket having 250 volts, single phase, 3-pin/2-pin out-let and power socket of 13/15/16amps on board including necessary connection and fixing screws, PVC tape etc. all complete as per drawing, direction and full satisfaction of the Bank authority.				
	a) 2-pin (5/10) amps combined socket	52	Nos		
	b) 13amps Multi socket	415	Nos		
	c) 3-pin round (15amps) combined socket	6	Nos		
	d) Single telephone socket	123	Nos		
<b>43</b>	<b>Light Fitting (imported):</b>				
	Supplied, fitting & fixing of wall or ceiling mounted incandescent light point like wall bracket, saucer light, PL light, security light, mirror light, high presser halide light, halogen light, garden light, T-5 LED light etc. including necessary connection and fixing screws, royal plug etc. all complete as per drawing, direction and full satisfaction of the Bank authority.				
	a) Supply, fitting & fixing of <b>20watt LED Panel light Only</b> all complete as per direction and full satisfaction of the Bank authority.	400	Nos		
	a) Supply, fitting & fixing of <b>5watt LED Spot light Only</b> all complete as per direction and full satisfaction of the Bank authority.	200	Nos		
	d) Supply, Fitting & fixing of best quality <b>T-5 LED tube light (12/18 watt)</b> including energy saving environmental protection efficient ( China) voltage/frequency: 220-240V/50-60Hz day light/warm white all complete as per direction and full satisfaction of the Bank authority.	700	Nos		
	d) Supply, Fitting & fixing of best quality <b>Glass Panel Light 20 Watt</b> including energy saving environmental protection efficient ( China) voltage/frequency: 220-240V/50-60Hz day light/warm white all complete as per direction and full satisfaction of the Bank authority.	300	Nos		
	d) Supply, Fitting & fixing of best quality <b>Hanging Light 20 Watt</b> including energy saving environmental protection efficient ( China) voltage/frequency: 220-240V/50-60Hz day light/warm white all complete as per direction and full satisfaction of the Bank authority.	40	Nos		
	e) Supply, Fitting & fixing of best quality light motion sensor	100	Nos		
<b>Sub-total of Electric Works (BDT)</b>					

SL	Description	QTY	Unit	Unit Rate	Amount (BDT)
<b>J. Miscellaneous Work</b>					
44	<b>HORIZONTAL ROLLER BLINDS :</b> Supply, fitting & fixing of imported (China) best quality 125mm wide vertical blinds of approved color (Branch and Priority Banking) with all imported accessories such as aluminum head rail, head & end cap set, rod till, stopper, runner, spacer (link) handling cod, controlling chain, link chair, bottom weight plate, bottom chain, cord weight and glass fiber fabrics/available etc as per approved color etc. all complete as per Bank standard and full satisfaction of the Bank authority.	3850	Sq. ft		
45	<b>VERTICAL METAL GRID FRAME</b> Supply, fitting & fixing Metal Grid Frame For Plants made of 25mm x 25mm MS Box, with Heat Paint Finish all complete as per design, Bank standard and full satisfaction of the Bank authority.	180	Sq. ft		
46	<b>OFFICE PLANTS</b> Supply, Fitting & Fixing Tree on the Vertical Grid Frame trees With Tree,Ready Mix Soil & 7" Plastic Tob(Bangol/RFL) .all complete as per Bank standard and full satisfaction of the Bank authority.	340	Nos		
47	<b>PVC FLOOR MAT FOR ENTRY</b> Supply, fitting & fixing of imported (China) best quality PVC floor mat of approved color/grey/ash color, solid bottom, mesh type upper portion, cutting with fine finish etc. all complete as per Bank standard and full satisfaction of the Bank authority.	250	Sq. ft		
<b>Sub-total of Miscellaneous Work (BDT)</b>					
<b>K. Office Furniture Work</b>					
<b>COUNTRY MANAGER ROOM :</b>					
48	<b>Executive TABLE:</b> Supply, fitting and fixing of Imported Executive Desk of high quality with Korea/Malaysia/China Origin all complete as per approval and full satisfaction of the Bank Authority.	1	Nos		
49	<b>Executive CHAIR:</b> Supply, fitting and fixing of high quality imported chair with Brand: Merryfair, Model Delphi-509, Malaysia Origin or Equivalent, high-back chair with headrest, all swivel chair models employ a fourpoint synchronised recline mechanism featuring gas seat height control, recline-tension adjustment and stepless reclinelock, the backbone supports are diecast aluminium in a smooth polished finish, 70cm diameter five-point base(V) in black polyamide (nylon) comes as standard all complete as per approval and full satisfaction of the Bank Authority.	1	Nos		

SL	Description	QTY	Unit	Unit Rate	Amount (BDT)
50	<b>VISITOR AND MEETING CHAIR:</b> Supply, fitting and fixing of high quality imported chair with Brand: Merryfair, Model Delphi-509, Malaysia Origin or Equivalent, high-back chair, all swivel chair models employ a fourpoint synchronised recline mechanism featuring gas seat height control, recline-tension adjustment and stepless reclinelock, backbone supports are diecast aluminium in a smooth polished finish, 70cm diameter five-point base(V) in black polyamide (nylon) comes as standard all complete as per approval and full satisfaction of the Bank Authority.	6	Nos		
51	<b>MEETING TABLE :</b> Supply, fitting and fixing of imported meeting table of high quality with Korea/Malaysia/China Origin, 1200mm dia table top with a combination of solid wood and engineered wood, metal leg support all complete as per approval and full satisfaction of the Bank Authority.	1	Nos		
52	<b>SINGLE SEATER SOFA :</b> Supply, fitting & fixing of "Single Seater Sofa" - Imported of size :L-760 x W-840mm best quality fabric and Oak wooden legs. Sofa is made of best quality wooden frame, spring covered with high quality foam and joined together complete (inc. materials cost, labour cost and other all charges) in all complete as per design, direction and full satisfaction of the Bank authority.	3	Nos		
53	<b>ROUND SIDE TABLE :</b> Supply, fitting & fixing square shaped 460mm dia "Round Side Table" made with Chiitagong Teak Wooden Leg with lacquer polish and top with combination of best quality 18mm Marble Top-polished complete (inc. materials cost, labour cost and other all charges) in all complete as per design, direction and full satisfaction of the Bank authority.	2	Nos		
54	<b>CONFERENCE TABLE 01:</b> Supply, fitting & fixing of Conference Table 3900mm x 1200mm made 25 mm thickness Chittagong Teak Shegun Wood, 18mm Gorjon Board for Table Top with best quality Lacquer Spray Paint finish, with Shegun Border on the edging, with 75mm x 50mm MS box frame and 50mm x 50mm MS box Beam with Heat Spray Finish, power grommets, cable tray and snake including all accessories, material, labour cost and all other charges all complete as per design, direction and full satisfaction of the Bank authority.	1	Nos		

SL	Description	QTY	Unit	Unit Rate	Amount (BDT)
55	<p><b>CONFERENCE TABLE 02:</b> Supply, fitting &amp; fixing of Conference Table 3150mm x 1200mm made 25 mm thickness Chittagong Teak Shegun Wood, 18mm Gorjon Board for Table Top with best quality Lacquer Spray Paint finish, with Shegun Border on the edging, with 75mm x 50mm MS box frame and 50mm x 50mm MS box Beam with Heat Spray Finish, power grommets, cable tray and snake including all accessories, material, labour cost and all other charges all complete as per design, direction and full satisfaction of the Bank authority.</p>	1	Nos		
56	<p><b>ROUND MEETING TABLE :</b> Supply, fitting and fixing of imported meeting table of high quality with Korea/Malaysia/China Origin, 1200mm dia table top with a combination of 18mm Laminated Board top, metal leg support all complete as per approval and full satisfaction of the Bank Authority.</p>	2	Nos		
57	<p><b>WORKING TABLE :</b> Supply, fitting &amp; fixing of <b>Working Table with in-built drawer unit</b> made of 18 mm thickness laminated board (color: Partex - Albino Oak/Havana) with melamine resin film under short cycle process both 02 mm PVC edging cover (color: imported-Albino Oak/Havana) all around the top, black stopper at leg, hanging bit, L clamps, screw, nails, handle(China), lock(China), channels (China), auto closing conceal cobja (China), magnet lock, including best quality of hardware materials etc. all complete as per design, direction and full satisfaction of the Bank authority.</p>				
	<p><b>a) Table 01 (Workstation Desk):</b> 1200 mmX 600 mm X 800 mm Drawer Unit: 450mm x 450mm x 700mm</p>	69	Nos		
	<p><b>b) Table 02 (Workstation Desk):</b> 1500 mmX 600 mmX 800 mm Drawer Unit: 450mm x 450mm x 700mm</p>	8	Nos		
	<p><b>c) Table 03 (Senior Desk) with Drawer Unit:</b> Table : 1650 mm x 600 mm x800 mm      Drawer Unit: 450mm x 450mm x 700mm</p>	6	Nos		



SL	Description	QTY	Unit	Unit Rate	Amount (BDT)
60	<p><b>SENIOR WORKING TABLE :</b> Supply, fitting &amp; fixing of <b>Working Table with in-built side return unit</b> made of 18 mm thickness laminated board (color: Partex - Albino Oak/Havana) with side return 18mm granite table top with molding, melamine resin film under short cycle process both 02 mm PVC edging cover (color: imported-Albino Oak/Havana) all around the top, black stopper at leg, hanging bit, L clamps, screw, nails, handle(China), lock(China), channels(China), auto closing conceal cobja (China), magnet lock, including best quality of hardware materials etc. all complete as per design, direction and full satisfaction of the Bank authority.</p>				
	<p><b>Table 04 (Senior Desk) with Side Return :</b> Table: 1650 mm x600 mm x 800 mm Side Return: 1050 mm x 400 mm x 800mm.</p>	7	Nos		
	<b>CHAIR</b>				
58	<p><b>WORKSTATION CHAIR:</b> Supply, fitting and fixing of high quality imported chair with Korea/Malaysia/China Origin, high-back chair, adjustable lumbar support, fixed armrest, multi-locking 3-step adjustment, tilting strength adjustable etc. all complete as per approval and full satisfaction of the Bank Authority.</p>	79	Nos		
59	<p><b>SENIOR WORKSTATION CHAIR:</b> Supply, fitting and fixing of high quality imported chair with Korea/Malaysia/China Origin, high-back chair, adjustable lumbar support, armrest height/front/back/left/right, multi-locking 3-step adjustment, adjustable tilting strength and seat plate depth etc. all complete as per approval and full satisfaction of the Bank Authority.</p>	13	Nos		
60	<p><b>SENIOR WORKSTATION VISITOR CHAIR:</b> Supply, fitting and fixing of high quality imported chair with Korea/ Malaysia/ China Origin, high-back chair, lumbar support, fixed armrest, 1-step adjustment, tilting strength adjustable etc. all complete as per approval and full satisfaction of the Bank Authority.</p>	26	Nos		
61	<p><b>CONFERENCE ROOM CHAIR:</b> Supply, fitting and fixing of high quality imported chair with Korea/Malaysia/China Origin, high-back chair, adjustable lumbar support, armrest height/front/back/left/right, multi-locking 3-step adjustment, adjustable tilting strength and seat plate depth etc. all complete as per approval and full satisfaction of the Bank Authority.</p>	20	Nos		

SL	Description	QTY	Unit	Unit Rate	Amount (BDT)
62	<b>MEETING ROOM CHAIR:</b> Supply, fitting and fixing of high quality imported chair with Korea/Malaysia/China Origin, high-back chair, adjustable lumbar support, fixed armrest, multi-locking 3-step adjustment, tilting strength adjustable etc. all complete as per approval and full satisfaction of the Bank Authority.	10	Nos		
63	<b>SINGLE SEATER SOFA :</b> Supply, fitting & fixing of "Single Seater Sofa" for Waiting Area and Conference Room of size :L- 760 x W-840mm fully upholstered with artificial leather or fabric. Sofa is designed with wooden legs. Sofa is made of best quality wooden frame, spring covered with high quality foam and joined together complete (inc. materials cost, labour cost and other all charges) in all respect as per approval and full satisfaction of the Client.	8	Nos		
64	<b>CABINETS:</b> Supply, fitting & fixing of cabinet made of 18 mm thickness laminated board (color: Partex - Albino Oak/Havana) with melamine resin film under short cycle process both 02 mm PVC edging cover (color: imported-Albino Oak/Havana) all around the top, hanging bit, L clamps, screw, nails, handle(China), lock(China), channels(China), auto closing conceal cobja (China), magnet lock, including best quality of hardware materials etc. all complete as per design, direction and full satisfaction of the Bank authority.				
	<b>e) Cabinet 01 (Type A):</b> 1200 mmX 400 mmX1000 mm	23	Nos		
	<b>f) Cabinet 01 (Type B):</b> 1200 mmX 400 mmX 1375 mm	9	Nos		
	<b>i) Cabinet 01 (Type E):</b> 1200 mmX 400 mmX 1300 mm	4	Nos		
	<b>j) Cabinet 02:</b> 1200 mm X400 mm X2225 mm	33	Nos		
	<b>k) Cabinet 03:</b> 1200 mmX 400 mmX 2400 mm	2	Nos		
	<b>l) Dining Table :</b> 600 mmX 600 mmX 750 mm	7	Nos		
	<b>m) Hanging Cabinet :</b> 4800 mmX 400 mmX 1000 mm	5	Nos		

SL	Description	QTY	Unit	Unit Rate	Amount (BDT)
65	<p><b>CABINETS:</b> Supply, fitting &amp; fixing of cabinet made of 18 mm thickness laminated board (color: Partex - Albino Oak/Havana) melamine resin film under short cycle process both 02 mm PVC edging cover (color: imported-Albino Oak/Havana) all around the top, hanging bit, L clamps, screw, nails, handle(China), lock(China), channels(China), auto closing conceal cobja (China), magnet lock, including best quality of hardware materials etc. all complete as per design, direction and full satisfaction of the Bank authority.</p>				
	<b>g) Cabinet 01 (Type C):</b> 1200 mmX 400 mmX 1025 mm	5	Nos		
	<b>h) Cabinet 01 (Type D):</b> 2400 mmX 400 mmX 1300 mm	2	Nos		
66	<p><b>OVERHEAD CABINETS: OPERATIONS</b> Supply, fitting &amp; fixing of cabinet made of 18 mm thickness laminated board (color: Partex - Albino Oak/Havana) with 50mm X 25mm main support frame and 25mm x 25mm internal frame of MS Box 3mm thickness with Heat Spray Paint finish, melamine resin film under short cycle process both 02 mm PVC edging cover (color: imported-Albino Oak/Havana) all around the top, hanging bit, L clamps, screw, nails, handle(China), lock(China), channels(China), auto closing conceal cobja (China), magnet lock, including best quality of hardware materials etc. all complete as per design, direction and full satisfaction of the Bank authority.</p>	70	Sq. ft		
67	<p><b>Tea Room &amp; Toilet Basin Black Granite Counter (Height 850mm) :</b> Supply, fitting &amp; fixing of 18 mm thick Black granite slab having 18mm height nos surround the open areas to protect water dropping on 62mm thick RCC slab (1:2:4) with 19 mm thick cement mortar (1:2) including necessary 125mm brick wall support, laying, cutting, grinding, molding and polishing the granite, proper pointing all complete as per Bank standard and full satisfaction of the Bank authority.</p>	11	Rft		
68	<p><b>RECEPTION COUNTER (Height 1100mm) :</b> Supply, making, fitting &amp; fixing of Reception Counter 3600 mm x 600mm made 18 mm gorjon ply board with 18mm marble on the counter service top and front face with hidde. light gutter, imported high pressure laminate sheet (HPL) pasted on the remaining body with drawer unit (Please see the details in furniture drawings) including all materials, accessories, labour costs and charges, nuts, screws, bolts, strong adhesive expoxy glue etc. as per design, Bank standard and full satisfaction of the Bank Authority.</p>	15	Rft		

SL	Description	QTY	Unit	Unit Rate	Amount (BDT)
69	ROOM SIGNAGE: Supply, fitting and fixing of Room Signage with the provided Graphics as per Design made of 18mm commercial board with Docu Spray Paint finish (Color: Matte Grey), white acrylic letter fonts and graphics including all accessories, materials, labour costs and charges all complete as per drawing, Bank Standard and full satisfaction of the Client.	45	Nos		
70	LOGO: Supply, fitting & fixing of HBL Logo as per design and drawings all complete as per standard and full satisfaction of the Client.	1	Nos		
<b>Sub-total of Furniture &amp; Fixtures (BDT)</b>					

## **Grand Total (A+B+C+D+E+F+G+H+I+J+K)**

IN WORDS : TAKA

### **NOTES:**

- 1 The Vendor(s)/contractor must visit the site before quoting for the line items of this BoQ.
- 2 All the material needs to be approved by Habib Bank Limited authority before the work start .
- 3 The vendors/ Contractor must submit the estimated work chart of interior fit out work of proposed Country Office.