

Bill of Quantity (BoQ)

Interior Fit-out Works of Main Branch of HBL Bangladesh

Address: Autograph (Level 04), 67 & 68 Kemal Ataturk Avenue, Banani, Dhaka 1213

SUMMARY OF SCHEDULE OF ITEMS	AMOUNT
A. Civil Works	BDT
B. Paint Works	BDT
C. Feature Panel Work	BDT
D. Partition Work	BDT
E. Floor Finishing Work	BDT
F. Ceiling Work	BDT
G. Door Work	BDT
H. Plumbing & Sanitary Work	BDT
I. Electrical Works	BDT
J. Miscellaneous Work	BDT
K .Furniture Work	BDT
TOTAL AMOUNT	BDT

In Word (Taka) :

DATE : _____

NAME OF THE COMPANY : _____

NAME OF THE OWNER : _____

COMPANY SEAL :

AUTHORIZED PERSON : _____ **SIGNATURE** _____

ATTESTED BY THE OWNER : _____ **SIGNATURE** _____

Schedule of Items
Interior Fit-out Work of Proposed Main Branch of HBL Bangladesh

SL	Description	QTY	Unit	Rate	Amount (Taka)
A.	Civil Works				
1	250mm BRICK WORK : Supply, fitting & fixing Brick work with 1st class brick (Size: 237mmX125mmX68mm) in cement sand (F.M. 1.2) mortar (1:6) in any structure in/c racking out joints, cleaning and soaking the brick at least for 24 hrs before use, filling the interstices with mortar, water, electricity, curing at least for 07 (Seven) days with scaffolding etc. all complete as per Bank standard and full satisfaction of the Bank authority.	180	Sq. ft		
2	125mm BRICK WORK: Supply, fitting & fixing Brick work with 1st class brick (Size: 237mm X125mm X68mm) in cement sand (F.M. 1.2) mortar (1:6) in any structure in/c racking out joints, cleaning and soaking the brick at least for 24 hrs before use, filling the interstices with mortar, water, electricity, curing at least for 07 (Seven) days with scaffolding etc. all complete as per Bank standard and full satisfaction of the Bank authority.	1450	Sq. ft		
3	PLASTER WORK: Supply, fitting & fixing Minimum 12mm @ wall, 6mm @ roof thick plaster with cement sand plastering (F.M. 1.2) plaster (1:4) best quality cement to walls both inner & outer surfaces. R.C.C. surfaces finishing corners and edges including washing of sand cleaning the surface, scaffolding, water, electricity and curing at least for 07 (Seven) days etc. all complete as per Bank standard and full satisfaction of the Bank authority.	3500	Sq. ft		

SL	Description	QTY	Unit	Rate	Amount (Taka)
4	<p>RCC WORKS : (Wall 250mm and flr & Roof 150mm) Double Layer Reinforcement cement concrete works using wooden/steel shutter with minimum cement content relates to mix ratio 1:1.5:3 having minimum f'y =4 Ksi, and satisfying, specified compressive strength f'c =3.0 Ksi at 28 days on standard cylinders as per standard practice of code ACI/BNBC/ASTM and cement conforming to BDS EN-197-1-CEM 1 (52.5N)/ ASTM-C 150 Type-1, best quality coarse sand (25% quantity of the best local sand (F.M.-1.2) and 75% quantity of Sylhet sand or coarse sand of equivalent (F.M.-2.2) and 20mm down well grade stone chips conforming to ASTM C-33, masking, placing shutter in position and maintaining true to plumb, making shutter water-tight properly, placing reinforcement in position; mixing standard mixer machine with hoper fed by standard measuring boxes, casting in forms, compacting by vibrator machine, 18mm dia 04nos PVC pipe for CCTV, Fire-Alarm, electric etc and curing at least for 28 days, removing centering- shuttering after specified time approved; including cost of water , electricity, testing charges of materials and cylinders, other charges etc all complete as per approval of the bank authority.</p> <p><u>[The contractor must supervise the vault and locker room construction work by an expert engineer preferably by a member of MIEB. Who will certifiy the satisfactory level of work. You must submit the certificate with the bill.]</u></p>	420	Cft		
5	RCC Works for Lintel: (150mm x 150mm)	60	Rft		
6	<p>Tea Room Basin Black Granite Counter (Height 850mm) : Supply, fitting & fixing of 18 mm thick Black granite slab having 18mm height nos surround the open areas to protect water dropping on 62mm thick RCC slab (1:2:4) with 19 mm thick cement mortar (1:2) including necessary 125mm brick wall support, laying, cutting, grinding, molding and polishing the granite, proper pointing all complete as per Bank standard and full satisfaction of the Bank authority.</p>	11	Rft		

SL	Description	QTY	Unit	Rate	Amount (Taka)
7	<p>TELLER COUNTER (Height 1050mm) : Supply, making, fitting & fixing of teller counter made of 125mm RCC wall with plaster to support the counter service top RCC slab (with proper support for service top slab), on the counter service top slab 18mm thick 600mm wide Parleto Sicily marble, laid over 62mm thick RCC slab (1:2:4).The marble top will drop by 300mm [Slope minimum 150mm] at front side & 100mm@ inside of the counter which will hide a T-5 tube light rail, imported laminate paper (SHIBU Sheet) pasted on 12mm thick slanting partex board covering over brick wall hiding a T-5 LED tube-light rail, which will be divided in equal parts, All through the lower part 125mm wide S.S. sheet pasted on the brick wall. Working top of inside counter made of 25mm, 18mm laminated particle board (Brand: Partex-light cherry) of 550mm width top etc. with drawer unit (Please see the details in furniture section), each counter divider (18mmX62mmX550mm) and keyboard tray (china), cable passing cap (china) alarm switch for all counter as per Bank standard and full satisfaction of the Bank Authority.</p>	11.5	Rft		
Sub-total of Civil Works (BDT)					
B	Paint Works				
8	<p>PLASTIC PAINT (Berger) : Supply, fitting & fixing Plastic emulsion paint of approved best quality and color delivered from authorized local agent of the manufacturer in a sealed container, applying to wall and ceiling in three coats over a lime putty of branch specified brand applied on primer or sealer elapsing specified time for drying/recoating including cleaning drying, making free from dirt, grease, wax, removing all chalked and scaled materials, fungus, mending good the surface defects, sand preparing the surface and necessary scaffolding, spreading by brush/roller/spray etc. All complete as per bank standard and full satisfaction of the bank authority.</p>	3500	Sq. ft		
Sub-total of Paint Works (BDT)					

SL	Description	QTY	Unit	Rate	Amount (Taka)
C	Feature Panel Work				
9	<p>Rolling Shutter : Supply, fitting & fixing of rolling shutter of any design and shape made of 24SWG G.P. sheet unit minimum 69mm width having 10mm and 12mm dia circular folding at ends, rolled in machine, locked together properly to form rolling shutter, top of the shutter to be fitted with circular spring box made of 22 BWG sheet, containing best quality spring made in China, nutted with 38mm G.I. pipe at one end and the other end nutted to shutter including fitting the G.I. pipe again with 375mmX300mmX6mm pankha at ends with side guide channel (side channel consist of 50mmX100mmX6mm M.S. plate with 2mmX19mmX3mm F.I. bar, middle channel consist of 2mmX150mmX6mm M.S. plate with 2mmX19mmX6mm fixed to wall or column with clamps embedded in RCC part by cement concrete (1:2:4) including cutting hole (minimum 3mmX25mmX6mm) mending the damages, finishing, curing, bottom end of shutter fitted to folded G.P. sheet (min 125mm width in two layers) which is again fitting to 25mmX25mmX3mm angle, providing handle with F.I. bar 25mmX6mm and locking arrangement in both sides, painting three coats with approved color and brand(Berger) of synthetic enamel paint over a coat of priming, view finder etc. all complete as per Bank standard and full satisfaction of the bank authority.</p>	200	Sq. ft		
10	<p>CONCRETE FEATURE WALL : Supply, fabrication & installation of approved color (4mm thick) aluminum composite panel (Alucobond/Alcopenl/Alcopolic/Bafoni) as per US Architectural Aluminum Manufacturer's Association (AAMA) in column, beam and wall surface providing with 44mmX44mmX1.5mm MS Box @ ceiling, 25mmX25mmX1.5mm @ wall, column, 18mm aluminum angle including supply of necessary hardware, consumables, scaffolding etc. fitted with necessary accessories like rivet, screw, rowel bolt, black rubber in groves, welded framing etc. all complete as per design, direction and full satisfaction of the Bank authority.</p>	300	Sq. ft		
Sub-total of Panel Work (BDT)					
D	Partition Work				
11	<p>10 MM GLASS PARTITION WITH U Channel: Supply, fitting & fixing glass partition made of 10 mm Tempered Glass with 25mmX25mm aluminum U channel in all sides of approved brand (KAI/FUWANG) and color with edge polish in vertical portion of glass, water color silicon gum by using masking tape including all other accessories and hardware etc. all complete as per Bank standard and full satisfaction of the Bank authority.</p>	420	Sq. ft		

SL	Description	QTY	Unit	Rate	Amount (Taka)
12	75mm THICK FULL HEIGHT PARTITION :				
	Supply, fitting & fixing of 12mm thick both side gypsum board (China) with best quality 1.5mm X 75mm C channel frame, at 600X600mm in grid suspended from ceiling, roof, floor, RCC and wall or beam by rowel plug & 75mm screw, nail etc with 03 coat of paint All complete as per Bank standard and full satisfaction of the Bank authority.	440	Sq. ft		
Sub-total of Partition Work (BDT)					
E.	Floor Finishing Work				
13	HOMOGENOUS MIRROR POLISH TILES (LIGHT) : Supply, fitting & fixing of imported 700mmX700mm (China) Homogeneous Mirror polished Tiles of approved on floor with 65 mm thick cement sand (F.M. 1:2) mortar(1:3) and raking out the joints with respective jointer filter and binder including cutting, laying and hire charge of machine and finishing with care etc including water electricity and other charges all complete with care and finish the pointing work including 100mm height skirting etc. 50mm width saffron color border tiles , 300mm width black tiles surrounding the column will have to be installed in front of the teller counter with 07 days curing etc. all complete as per Bank standard and full satisfaction of the Bank authority.	1400	Sq. ft		
14	TOILET WALL TILES (Branch) : Supply, fitting & fixing of 250mmX400m (RAK/Great wall) ceramic tiles in wall of approved color with 20 mm thick cement sand (F.M. 1:2) mortar (1:3) base and raking out the joints with respective joint filter and binder including cutting, laying and hire charge of machine and finishing with care etc including water, electricity and other charges All complete as per Bank standard and full satisfaction of the Bank authority.	180	Sq. ft		
15	TOILET FLOOR TILES (Branch): Supply, fitting & fixing of 300mm X 300mm (RAK/CBC/ FUWANG) homogenous tiles of approved color on floor with 65mm thick cement (F.M. 1:2) mortar (1:3) base and raking out the joints with respective joint filter and binder including cutting, laying and hire charge of machine and finishing with care etc including water, electricity and other charges, 07 days curing etc all complete as per Bank standard and full satisfaction of the Bank authority.	65	Sq. ft		

SL	Description	QTY	Unit	Rate	Amount (Taka)
16	<p>Mate Tiles 300mm X300mm : Only fitting & fixing of 300mm X 300mm (existing) homogenous tiles of approved color on floor with 65mm thick cement (F.M. 1:2) mortar (1:3) base and raking out the joints with respective joint filter and binder including cutting, laying and hire charge of machine and finishing with care, 07 days curing etc. including water, electricity and other charges All complete as per Bank standard and full satisfaction of the Bank authority.</p>	340	Sq. ft		
17	<p>Wooden Floor Tiles : Supply, fitting & fixing of wooden homogenous tiles of approved color on floor with 65mm thick cement (F.M. 1:2) mortar (1:3) base and raking out the joints with respective joint filter and binder including cutting, laying and hire charge of machine and finishing with care, 07 days curing etc. including water, electricity and other charges All complete as per Bank standard and full satisfaction of the Bank authority.</p>	525	Sq. ft		
Sub-total of Efloor Finishing Work (BDT)					
F	Ceiling Work				
18	<p>LOUVRE DESIGN BOARD CEILING: Supply, fitting & fixing of Designed Louvre Ceiling made with 18mm Commercial Board (Partex or equivalent) premium quality false ceiling and 03 (Three) coats of plastic paint over primer coat, putty, racking out joints etc. Also including powder coated T-bar of section 25mmx38mm and L-angle of section 25mmx25mm at edges, at 600mmx600mm grid suspended ceiling by rowel plug iron angles 12 SWG G.I. wire, screws, hooks, nails etc. maintaining straight lines and desired finished level at bottom face with vertical or beams by electric drill machine damage if any during the materials, accessories, scaffolding, labor for Installation etc. all complete as per Bank standard and full satisfaction of the Bank authority.</p>	475	Sq. ft		
19	<p>PLAIN DROP WOODEN CEILING: Supply, fitting & fixing of 12mm thick both gypsum board (China) with best quality 1.5mm X 50mm C channel frame at 600X600mm in grid suspended from ceiling, roof, floor, RCC and wall or beam by rowel plug & 75mm screw, nail etc and 03 (Three) coats of plastic paint over primer coat, putty, racking out joints etc. All complete as per Bank standard and full satisfaction of the Bank authority.</p>	500	Sq. ft		

SL	Description	QTY	Unit	Rate	Amount (Taka)
20	GROOVE MINERAL BOARD CEILING: Supply, fitting & fixing of 600mm X600mm X 15 mm grove mineral board (China) false ceiling over powder coated T-bar of section 25mmx38mm and L-angle of section 25mmx25mm at edges, at 600mmx600mm grid suspended ceiling by rowel plug iron angles 12 SWG G.I. wire, screws, hooks, nails etc. maintaining straight lines and desired finished level at bottom face with vertical or beams by electric drill machine damage if any during the materials, accessories, scaffolding, labor for Installation etc. all complete as per Bank standard and full satisfaction of the Bank authority.	650	Sq. ft		
21	WOODEN DROP for Fixed Glass : Supply, fitting & fixing of plain wooden drop over the glass partition suspended from existing R.C.C. slab of the building at the level of 2550mm (or as per direction) height made of 12mm thick white partex over frame of section 75mmX38mm at 600X600mm in grid suspended from ceiling or roof with 50mmx25mm best quality seasoned Garjon wood section, 75mm screw, nails, rowel plug, fevicol aica and 03(Three) coats of plastic paint over primer coat , putty, racking out joints etc. including AC side covering. all complete as per Bank standard.	230	Rft		
Sub-total of Ceiling Work (BDT)					
G.	Door Work				
22	TEMPERED DOOR (900mmx2400mm): New Supply, fitting & fixing of imported 10 mm glass door shutter (V.V.P) with door closer at lower side, 1200mm round stainless steel handle, lower side lock, hinge, 02 nos stopper (China-Half round SS, rubber coating) & other accessories etc. all complete as per Bank standard and full satisfaction of the authority.	7	Nos		
23	FLUSH DOOR SHUTTER WITH FRAME : Supply, fitting & fixing of 39mm thick and having density 400kg/cum solid particle board single leaf flush door (Brand: Partex) of best quality teak veneered partex door, frame by best quality seasoned Gorjon wood 62mmx125mm section with the supply of best quality all hardware, 100mm metal hinges, clamps, sitkani, coal tarring of frame including, 02 nos stopper (China-Half round SS, rubber coating), 150mm long tower bolt (Imported), & polish finish (of approved color) all complete as per direction and full satisfaction of the Bank Authority.	5	Nos		
24	Fire Door : Supply, fitting & fixing of UL Approved, Fire Rating: 120 Minutes, Size: L-1100 x H-2400 mm, Door Model: Multiline Industries Ltd, Door Core: Rock wool with density 100 kg/m ³ , Door Sheet Thickness: 1.6mm, Door Thickness: 50mm. all complete as per Bank standard and full satisfaction of the authority.	1	Nos		
Sub-total of Door Work (BDT)					

SL	Description	QTY	Unit	Rate	Amount (Taka)
H	Plumbing & Sanitary Work				
25	COMMODE WITH LOW DOWN (Branch): Supply, fitting & fixing of combi commode with low down (RAK- Orient) set of approved color/ Ivory color with other fittings etc. all complete as per full satisfaction of the Bank authority.	1	Nos		
26	COUNTER/ PADEL STAND BASIN(Branch): Supply, fitting & fixing of basin (RAK –Karla & Mira) of approved color/ Ivory color with other fittings etc. all complete as per full satisfaction of the Bank authority.	1	Nos		
27	SOAP TRAY (RAK Accessories): Supply, fitting & fixing of soap tray of approved color/Ivory Color and quality with necessary hardware etc. all complete as per full satisfaction of the Bank authority.	1	Nos		
28	TOWEL RAIL (RAK Accessories): Supply, fitting & fixing of 600mm Towel rail of approved color/Ivory Color and quality with necessary hardware etc. all complete as per full satisfaction of the Bank authority.	1	Nos		
29	PAPER HOLDER (RAK Accessories): Supply, fitting & fixing of paper holder of approved color /Ivory color and quality with necessary hardware etc. all complete as per full satisfaction of the Bank authority.	1	Nos		
30	COMMODE SHOWER: Supply, fitting & fixing of commode shower (RAYA/Hyballi) of approved color/ ivory and quality with necessary hardware etc. all complete as per full satisfaction of the Bank authority.	1	Nos		
31	MIRROR with Frame/SS Knob: Supply, fitting & fixing 6mm thick mirror (900mm X 750mm) of best quality with necessary hardware etc. all complete as per full satisfaction of the Bank authority.	1	Nos		
32	STEEL SINK (Round): Supply, fitting fixing of single bowl stainless steel sink (size: 450mm dia) with heavy type (Singapore/Malaysia) CI steel brackets 40mm dia CP chain plug, 40mm dia CP waste, 40mm dia PVC waste pie with brass coupling (750mm length) including making hole in wall and floor and mending good the damages, finishing with cement mortar all complete as per full satisfaction of the Bank authority.	2	Nos		
33	SANITARY FITTINGS: Supply, fitting & fixing of toilet fittings of approved quality with necessary hardware etc. all complete as per full satisfaction of the Bank authority. (Nazma)				
	a) Tri Star Left Hand Sink Cock (Nazma)	1	Nos		

SL	Description	QTY	Unit	Rate	Amount (Taka)
	b) Six Corn Angle Stop Cock (Nazma)	10	Nos		
	c) Single Liver Wash Basin Mixer (Nazma)	1	Nos		
	d) Germany Style Bottle Tarff (Nazma)	1	Nos		
	e) Tri Star Twin One Bib Cock(Nazma)	1	Nos		
	f) Square SS Floor Grating Net (Wesda)	2	Nos		
	<p>g) Sanitary piping Works:</p> <p>i. Supply, fitting and fixing of 25mm/18mm G.I./Upvc pipe with all general fitting such as bend, elbow, socket, reducing socket, Tee, unions, jam-nuts, gate valve for each toilet and kitchen including cutting trenches where necessary and fitting the same with earth duly rammed and fixing in walls with holder, bats and making hole in floor, walls and consequent mending good the damages etc all complete from building main line to the desired areas of usage.</p> <p>ii. Supply fitting and laying up to depth of invert 100mm inside dia best quality UPVC C grade pressure soil pipe having specific gravity 1.3-1.45 and other physical, chemical, thermal, fire resistivity properties etc as per BSTI approved manufacturer standards or ASTM, BS/ISO/IS standards fitted & fixed in position with sockets, bends, door tee, elbow, Tee with all accessories such as solvent cement, round grating/domed roof grating etc <u>from the available line to wash rooms to the disposal line</u> all complete as per Bank standard and full satisfaction of the Bank authority.</p>	1	As Required		
Sub-total of Plumbing & Sanitary Work (BDT)					
I	Electric Work				
34	PVC Conduit (Pipe Fitting for AC water line, Electric, CCTV, Time Attendance, HT cable & Generator cable):				
	Supply, fitting & fixing of water grade PVC rigid/flexible conduit (Aziz Pipes or equivalent) of following sizes through brick wall, RCC slab, false ceiling etc including groove cutting, network pipe, necessary binding wire & fixing circular boxes, junction boxes, sockets, fish wire, all are accessories and including mending good all damages etc. all complete as per direction and full satisfaction of the Bank authority.				
	a) 18mm dia PVC Conduit	700	Rft		
	b) 25mm dia PVC Conduit	640	Rft		
	c) 18mm dia PVC Conduit	500	Rft		
	d) 18mm dia Flexible PVC Conduit	500	Rft		

SL	Description	QTY	Unit	Rate	Amount (Taka)
35	Cable (B.R.B or equivalent)				
	Supply, fitting & fixing of PVC insulated or PVC sheathed cable (Color-Red, yellow, black) through PVC conduit in concealed, Underground, surface including all necessary fitting, fixing PVC type, fish wire, soldering, connection etc. all complete as per direction and full satisfaction of the Bank authority				
	d) 1X10.0 rm (7-w) NYY Cable	280	Rft		
	e) 1X4.0 rm (7-w) BYA Cable	1312	Rft		
	f) 1X2.5 rm (7-w) BYA Cable	1312	Rft		
	g) 1X1.5 rm (7-w) Cable	2296	Rft		
	h) 02 pair telephone cable	328	Rft		
	i) Coaxial cable for dish line	328	Rft		
36	Earthing Wire (B.R.B or equivalent):				
	Supply, fitting & fixing ECC(Earth Continuity conductor) copper wire for earthing connection (Color-Green) through PVC conduit in concealed, Underground, surface including all necessary fitting , fixing PVC type, fish wire, soldering, connection etc. all complete as per direction and full satisfaction of the Bank authority				
	a) 1X10rm (7-w) BYA Cable ECC Wire (Green)	70	Rft		
	b) 1X4.0 rm (7-w) BYA ECC wire (Green)	656	Rft		
	b) 1X2.5 rm (7-w) BYA ECC wire (Green)	656	Rft		
37	Switch/Junction Box fitting:				
	Supply, fitting & fixing of different size of concealed boards/boxes (Brand– best quality local)in position including ebonite cover etc. In position with fixing of necessary, washers etc. all complete as per drawing, direction and full satisfaction of the Bank authority				
	a) Steel/MK Plastic box(1-Gang, 2-Gang, 3-Gang)	20	Nos		
	b) DB Box	1	Nos		
38	Fixing of SDB, BD and EDB boxes with indicator & selection switch:				
	a) Providing & fixing 400/440V, 50 Hz , TPMCCB, SPMCBs manufactured and tested in accordance with relevant IEC/VDE/NEMA/BS/JIS standard having minimum breaking capacity 25-KA with terminal over current and instantaneous electromagnetic short ckt. Release, necessary arrangement for fixing MCBs in/c stove enamel/grey hammer painting of board etc.				

SL	Description	QTY	Unit	Rate	Amount (Taka)
	iii. 40amps TP MCCB	1	Nos		
	iv. 10amps TP MCB (Air-Cooler)				
	v. 20amps SP MCB (Computer, printer, oven, electric kettle, fridge, photocopy, signboard & outdoor light)	3	Nos		
	vi. 16amps SP MCB	8	Nos		
	vii. 10amps SP MCB (lighting)	6	Nos		
39	M.K /Legrand Switch:				
	Supply, fitting & fixing of 250 votls 5/6amps(minimum) concealed type MK (Singapore) switch on steel/PVC/ junction MK board including necessary connection and fixing screws, PVC tape etc. all complete as per drawing, direction and full satisfaction of the Bank authority				
	a) 2-gang switch	15	Nos		
	b) 3-gang switch	12	Nos		
	c) 4-gang switch	10	Nos		
	d) DP Switch [20AMP] for signboard	2	Nos		
40	Legrand/M.K (Singapore) outlet and power socket:				
	Supply, fitting & fixing concealed type Legrand/MK (Singapore) sockethaving 250 volts, single phase, 3-pin/2-pin out-let and power socket of 13/15/16amps on board including necessary connection and fixing screws, PVC tape etc. all complete as per drawing, direction and full satisfaction of the Bank authority.				
	a) 2-pin (5/10) amps combined socket	10	Nos		
	b) 3- pin Multi (13amps) combined socket (Ligrand Mallia White)	35	Nos		
	c) 3-pin round (15amps) combined socket (Ligrand Mallia White)	10	Nos		
	d) Single telephone socket (Ligrand Mallia White)	4	Nos		
	e) Reutilization of existing sockets of old branch	0	Nos		
41	Light Fitting (imported):				
	Supplied, fitting & fixing of wall or ceiling mounted incandescent light point like wall bracket, saucer light, PL light, security light, mirror light, high presser halide light, halogen light, garden light, T-5 LED light etc. including necessary connection and fixing screws, royal plug etc. all complete as per drawing, direction and full satisfaction of the Bank authority.				

SL	Description	QTY	Unit	Rate	Amount (Taka)
	a) Supply, fitting & fixing of 12watt LED Spot light Only all complete as per direction and full satisfaction of the Bank authority.	64	Nos		
	a) Supply, fitting & fixing of 5watt LED Spot light Only all complete as per direction and full satisfaction of the Bank authority.	70	Nos		
	b) Supply, Fitting & fixing of best quality 1200mm T-5 LED tube light (18/20watt) including energy saving environmental protection efficient (China) voltage/frequency: 220-240V/50-60Hz day light/warm white all complete as per direction and full satisfaction of the Bank authority.	72	Nos		
42	Supply, fitting, fixing of Burglar Alarm Bell (Local) 150mm dia steel made with surrounding protective grill case having bell push with connection from the teller, bill pay, priority center and branch manager room including necessary accessories etc all complete as per approval of the bank authority.	1	Nos		
Sub-total of Electrical Works (BDT)					
J	Miscellaneous Work				
43	HORIZONTAL ROLLER BLINDS Supply, fitting and fixing of horizontal blinds made with aluminum foils/strips (China) of white color with supply of all materials such as head & bottom rail, rod till, head & bottom cap, gear box, stick, support end cap, cord drum and support, bracket, cord lock, cord equalizer, top holder, ladder cord, handling cord and aluminum foils etc. all complete as per Bank standard and full satisfaction of the Bank authority.	890	Sq. ft		
44	HBL LOGO SIGNAGE: Supplying, fitting and fixing of Signage Logo size 1200mm x 450mm as per design and drawings provided including all materials with SS accessories, cost and carriage of all materials, accessories, labour for installation and materials etc. all complete as per direction & full satisfaction of the Bank Authority.	3	Nos		
45	ROOM SIGNAGE: Supply, fitting and fixing of Room Signage with the provided Graphics as per Design made of 18mm commercial board with Docu Spray Paint finish (Color: Matte Grey), white acrylic letter fonts and graphics including all accessories, materials, labour costs and charges all complete as per drawing, Bank Standard and full satisfaction of the Client.	22	Nos		
46	FROSTED PAPER : Supply, fitting & fixing of Printed Frosted Paper As Per Design, Height 1200 mm all complete as per design, direction and full satisfaction of the Bank authority.	320	Sq. ft		

SL	Description	QTY	Unit	Rate	Amount (Taka)
47	PVC FLOOR MAT FOR ENTRY Supply, fitting & fixing of imported (China) best quality PVC floor mat of approved color/grey/ash color, solid bottom, mesh type upper portion, cutting with fine finish etc. all complete as per Bank standard and full satisfaction of the Bank authority.	40	Sq. ft		
Sub-total of Miscellaneous Work (BDT)					
K	Furniture Work				
48	EXECUTIVE TABLE : Supply, fitting & fixing of cabinet made of 25mm, 18 mm thickness laminated board (color: Partex - Albino Oak/Havana) with melamine resin film under short cycle process both 02 mm PVC edging cover (color: imported-light Albino Oak/Havana) all around the top, black stopper at leg, hanging bit, L clamps, screw, nails, handle(China), lock(China), channels(China), auto closing conceal cobja (China), magnet lock, including best quality of hardware materials etc. all complete as per design, direction and full satisfaction of the Bank authority.				
	a) Table 01 (Workstation Desk): 4'-0"x2'-0"x2'-8"	3	Nos		
	d) Table 04(Senior Desk): 5'-6"x2'-0"x2'-8" (2)3'-6"x1'-4"x2'-8"	4	Nos		
49	LOW HEIGHT CABINETS: Supply, fitting & fixing of cabinet made of 25mm, 18 mm thickness laminated board (color: Partex - Albino Oak/Havana) with melamine resin film under short cycle process both 02 mm PVC edging cover (color: imported- Albino Oak/Havana) all around the top, black stopper at leg, hanging bit, L clamps, screw, nails, handle(China), lock(China), channels(China), auto closing conceal cobja (China), magnet lock, including best quality of hardware materials etc. all complete as per design, direction and full satisfaction of the Bank authority.				
	a) Cabinet 01 (Type A): 4'-0" x 1'-4" x 3'-4"	2	Nos		
	b) Cabinet 01 (Type B): 4'-0" x 1'-4" x 4'-7"	2	Nos		
	c) Cabinet 03: 4'-0" x 1'-4" x 8'-0"	1	Nos		
50	Supply, fitting & fixing of " 2 Seater Sofa " for Waiting Area of size :L- 1800 x W-840mm fully upholstered with artificial leather or fabric. Sofa is designed with wooden legs. Sofa is made of best quality wooden frame, spring covered with high qulaity foam and joined together complete (inc. materials cost, labour cost and other all charges) in all respect as per approval and full satisfaction of the Client.	4	Nos		

SL	Description	QTY	Unit	Rate	Amount (Taka)
51	Supply, fitting & fixing of " 1 Seater Sofa " of size :L- 760mm x W-840mm fully upholstered with artificial leather or fabric. Sofa is designed with wooden legs. Sofa is made of best quality wooden frame, spring covered with high quality foam and joined together complete (inc. materials cost, labour cost and other all charges) in all respect as per approval and full satisfaction of the Client.	4	Nos		
52	Supply, fitting & fixing of round shaped 1065mm dia " Center Table " made with Chiitagong Teak Wooden Leg with lacquer polish and top with combination of best quality 18mm Marble Top-polished complete (inc. materials cost, labour cost and other all charges) in all respect as per approval of and full satisfaction of the Client.	2	Nos		
53	Supply, fitting & fixing square shaped 460mm dia " Round Side Table " made with Chiitagong Teak Wooden Leg with lacquer polish and top with combination of best quality 18mm Marble Top-polished complete (inc. materials cost, labour cost and other all charges) in all respect as per approval of and full satisfaction of the Client.	4	Nos		
54	Supply, fitting & fixing of " Workstation Chair " high quality imported chair with mesh backrest, lumbar support pad, armrest, height and seat adjustable and swivelable with SS polish legs revolving machine and structure, cushioning complete in all respect as per approval and full satisfaction of the Client.	10	Nos		
55	Supply, fitting & fixing of " Visitor Chair " high quality imported chair with mesh backrest, lumbar support pad, armrest, height and seat adjustable and swivelable with SS polish legs revolving machine and structure, cushioning complete in all respect as per approval and full satisfaction of the Client.	8	Nos		
56	Supply, fitting & fixing of " Meeting Chair " high quality imported chair with mesh backrest, lumbar support pad, armrest, height and seat adjustable and swivelable with SS polish legs revolving machine and structure, cushioning complete in all respect as per approval and full satisfaction of the Client.	4	Nos		
57	Supply, fitting & fixing of " Meeting Table ", size : 1200 mm dia, Made of combination of solid wood top and metal ms legs with grey heat paint finish all complete (inc. materials cost, labour cost and other all charges) in all respect as per approval of Authority and Engineer-in-charge.	1	Nos		

SL	Description	QTY	Unit	Rate	Amount (Taka)
57	SDB Board Paneling: Supply, fitting & fixing of SDB Board paneling with 25mm plain particle board (Brand: Partex/Amber), 50mmX25mm well-seasoned gorjan wooden frame, L clamps, screw, nails, handle (China), lock (China), magnet lock, 25mm stainless steel chain cobja (China), air passing hole, paint work including best quality of hardware materials etc. all complete as per design, direction and full satisfaction of the Bank authority.	40	Sq. ft		
Sub-total of Furniture Work (BDT).					
Grand Total (A+B+C+D+E+F+G+H+I+J+K) in BDT					

In words: Taka ...

NOTES:

- 1 The Vendor(s)/contractor must visit the site before quoting for the line items of this BoQ.
- 2 All the material needs to be approved by Habib Bank Limited authority before the work start .
- 3 The vendors/ Contractor must submit the estimated work chart of interior fit out work of proposed Country Office.
- 4 The rate should be including VAT & Taxes.