



Bill of Quantity (BoQ)

Repair and Renovation Work of HBL Chattogram Branch
Mokka Madinah Trade Center Center, 78 Agrabad C/A, Chattogram

SUMMARY OF SCHEDULE OF ITEMS	AMOUNT
A. Renovation of wash room block	BDT
B. Plumbing & Sanitary Work	BDT
C. Ceiling Works	BDT
D. Electrical Works	BDT
E. Furniture Items	BDT
F. Miscellaneous Work	BDT
TOTAL AMOUNT	BDT
VAT	Excluding

In Word (Taka) :

Name of the Company : _____

Authorized Person : _____

Signature : _____ Date _____

Company Seal

Schedule of Items

Repair and Renovation Work of HBL Chattogram Branch

SL	Particulars	Qty	Unit	Rate	Amount
A Renovation of Wash Room Block					
1	Dismantling work: Dismantling of the wash room walls, floor tiles & mortar as much as required for fitting of sanitary pipes. The dismantling work to be conducted with appropriate caution, and remove & shifting the debris from the site to external location.	1	job		
2	5" Brick work: Brick wall work with First Class Brick in cement mortar (1:4) in any structure in/c racking out joints, cleaning and soaking the brick at least for 24 hrs before use, filling the interstices with mortar, water, electricity.	120	sft		
3	Plaster work : Minimum 1/2 inch thick plaster with cement mortar (1:4) on walls both inner & outer surfaces. R.C.C. surfaces finishing corners and edges including washing of sand cleaning the surface & curing appropriate time.	60	sift		
4	Flush Door Shutter with Frame: Supply, fitting & fixing of 38mm thick and having density 400kg/cum solid particle board single leaf flush door (Brand: Partex or equivalent) of best quality teak veneered partex door, frame by best quality seasoned Gorjon wood 62mmx125mm section, along with the supply of best quality required hardware & accessories.	3	nos		
5	Tiles for wash room block; (TilesSize 2ft X 1ft) Supply, fitting & fixing of best quality (Grade-A) homogenous tiles (Venuss/ / DBL/ Charu) of approved color on floor with minimum 40mm thick cement, mortar (1:3) base and raking out the joints with respective joint filter and binder.	580	sft		
B Plumbing & Sanitary					
6	Comode with Low Down: Supply, fitting & fixing of combi commode with low down (RAK- Orient) set of approved color with other fittings etc.	2	nos		
7	Counter Top Basin: Supply, fitting & fixing of counter top basin with necessary civil works, marble top, and other required materials.	1	job		
8	Padestal Basin : Supply, fitting & fixing of basin (RAK –Karla & Mira) of approved color with other fittings etc.	1	nos		
9	Mirror with Frame and SS Knob: Supply, fitting & fixing 6mm thick mirror (4ft x 2.5ft) with Aluminium Section Frame (Grey) with necessary hardwares.	1	nos		
10	Hand towel Tissue Holder (Standard, as per sample, available at Country Office)	2	nos		
11	Tissue Paper Holder (Standard quality)	3	nos		
13	Commode Hand Shower: Supply, fitting & fixing of commode shower (RAYA/Hyballi) with necessary hardware.	3	nos		
14	Supply & Fitting of single Liver Wash Basin Mixer (Akij or RFL).	2	nos		
15	Supply & Fitting of Six Corn Angle Stop Cock	4	nos		
16	Supply & Fitting of Pillar Cock	2	nos		

SL	Particulars	Qty	Unit	Rate	Amount
17	Making of Abulution corner with necessary civil work and finishing.	1	job		
18	Square SS Floor Grating Net (Wesda)	3	nos		
19	4" UPVC Pipe supply & Fitting with Van Socket: Supply, fitting and fixing of 25mm/18mm G.I./Upvc pipe with all general fitting such as bend, elbow, socket, reducing socket, Tee, unions, jam-nuts, gate valve for 2 toilets.	1	job		
20	Water Line as per Lay out of the wash room 3/4" piping work with required accessories from the available line to wash rooms to the disposal line	1	job		
Sub-total of wash block renovation work					
C Ceiling Works					
21	Gypsum Board Ceiling (For BM Room & adjacent area) : Supply, fitting and fixing of 10 mm Engraved Gypsum board false ceiling over powder coated T-bar of section 1" X 1.5". and L-angle of section 1" X 1" at edges, at 2'-0" X 2'-0" grid suspended ceiling with all required materials related to fitting & fixing. Maintain the straight lines and desired finished as per the existing set-up.	280	sft		
22	Gypsum Board Ceiling (For Wash rooms) : Supply, fitting and fixing of 10 mm Engraved Gypsum board false ceiling over powder coated and with required with all required materials for fitting & fixing.	140	sft		
23	Wooden ceiling: Supply of new wooden ceiling as per require materials and dismantling as exiting board Proper care and precautions should be taken for the safety of the Building and full satisfaction of building authority	120	sft		
24	Grove Mineral board ceiling: Supply of new Mineral baord as with required materials including T-Bar section 1" X 1.5". and L-angle of section 1" X 1" at edgesand Dismantling the existing mineral boards and safe removal & shifting the debris to the external location.	1200	sft		
Sub-Total of Ceiling Works					
D Electrical works					
25	BYA FR Skin coated Cable (BRB) 1.5 rm: Supply, fitting & fixing of FR PVC insulated or PVC sheathed cable (Color-Red, black).	300	rft		-
26	Power Socket: Supply, fitting & fixing MK (Singapore) socket having 250 volts, single phase, 3-pin out-let and power socket of 13 amps on board including necessary connection and fixing.	6	nos.		
27	13amps Multi socket	3	nos.		
28	Lights : Supply, fitting of 13 watt LED lights with shade for wash Room	10	nos		
29	Supply and installation of sensor for wash room lights.	3	nos		
30	Electrcial power points for light and Desk table	12	nos		
31	Supply and installation of 13 watt LED lights	8	nos		

SL	Particulars	Qty	Unit	Rate	Amount
32	Supply and installation of Single telephone socket	2	nos		
33	Other costs related to Electrical works (Misc)	1	job		
Sub-total of Electrical works					
E Furniture Items					
34	Full Height File Cabinets: Supply, fitting & fixing of Full Height File Cabinet Made of 1" Melamine board (color: Partex - Albino/as per the sample and with nessary hardwares. Size: 4' x8' = 32 sft per Cabinet. Total 7 Nos.	7	nos		
35	Low Height File Cabinets: Supply, fitting & fixing of Full Height File Cabinet Made of 1" Melamine board (color: Partex - Albino/as per existing tables) Engineering in charge. Back side of New 2 Desks. 4' x 2.5' = 10 sft X 3 units.	3	nos		
36	Table with Side Return (Table size 4'-6" X 2'- 6", Side Return size - 3'-6" x 1'-4') : Made of 1" Melamine board (color: Partex - Albino/as per existing tables) with side return table top with molding, melamine resin film under short cycle process both 02 mm PVC edging cover (matching color: imported) all around the top. 3/4" thick gray color pertex board inside supports as per sample.	2	nos		
37	Workstation Chair Supply, fitting & fixing of "Workstation Chair" high quality imported chair with mesh backrest, lumbar support pad, armrest, height and seat adjustable and swivelable with SS polish legs revolving machine and structure.	14	nos		
38	Visitor Chair: Supply, fitting and fixing of high quality imported chair (Korea/ Malaysia/ China Origin). And as per apporved sample	4	nos		
39	02 Seater Sofa: Ready made Sofa, Brand - Otobi, as per approved sample and color.	2	nos		
40	Single Seater Sofa: Ready made Sofa, Brand - Otobi, as per approved sample and color.	2	nos		
Sub-total of Furniture Items					
F Miscellaneous works					
41	Plastic paints (Berger): Painting work in 3 coats of plastic paint of approved color and quality.	3500	sft		
42	Supply & installation of Roller Blind Supply, fitting & fixing of imported (China) best quality 125mm wide roller blinds with accesories; As per approved samle	260	sft		
43	Supply and fixing of white Tiles on Teller counter (As per existing sample)	8	rft		
44	Glass opening & Ceiling dismantling work	1	job		

SL	Particulars	Qty	Unit	Rate	Amount
45	Refitting of an existing table	1	job		
46	Floor Carpet tiles (imported 2ft X 2ft) with SS Transition	280	sft		
47	SDB Board Paneling Supply, fitting & fixing of SDB Board paneling with 25mm plain particle board (Brand: Partex/Amber), 50mmX25mm well-seasoned gorjan wooden frame, and with necessary hardware	30	sft		
48	Dimantling of mineral board ceiling of switch room and with good finishing with T and required materials	1	job		
49	Other Misc works (as per requirement of the branch)	1	job		
	Sub-Total of Miscellaneous Works				
	TOTAL AMOUNT (A+B+C+D+E+F) excluding VAT				

Amount in Word: